BRUHAT BANGALORE MAHANAGARA PALIKE

3BMP/2018-19/OW/WORK_INDENT31102/CALL-

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/09/2018-19, Date: 25.09.2018

Providing and fixing Street name boards in Ward No. 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of BHARATH S ( )	
				In Figures	In Words
1	24.41	KSRB 2-2.1 : Earth work excavation for foundation of building water sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of colds complete as per specifications.(Page No.5, Item No. 2.3)	Cum	80.0	Rupees Eighty Only
2	113	KSRRB M800-3. Direction and Place Identification Signs upto 0.9 sqm Size Board:-Manufacturing, supply and installation of retro- reflectorised cautionary, mandatory and informatory signboards made out of cube corner micro prismatic grade sheeting confirming to type XI standards of IRC :67:2012 specifications & fixed over 4 mm thick aluminium composite panel sheet having minimun 0.30 thick aluminium skin on both sides & fixed over a support frame of 25x25x3 mm MS angle and mounted on 75mm dia OR 75x75x6mm Mild steel angle of total height 2.70m with clear height of not less than 2.10 m from the ground level to the bottom of the sign board & 60 cm below ground level. The sign post should be painted with one coat of red oxide paint and white colour with brands of 30 cm height alternatively firmly fixed to the ground by means of foundation with M20 grade cement concrete of 45 cm x45 cm x 60 cm including cost & conveyance of all materials, equipment, machinery & labour with all leads and lifts, loading charges necessary for satisfactory completion of the work as directed by engineer in charge. 10 years warranty for retro reflective sheeting from the original sheeting manufacturer as per clause 6.9 in IRC 2012 & a certified copy of three years outdoor exposure report from an independent test lab for the product offered shall be obtained from the supplier.Page.No.182, Item No.24.30. PWD SR 2016-17	Sqm	7800.0	Rupees Seven Thousand Eight Hundred Only
3	148.93	KSRB 15-18.1 : Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications.., (Page No.121, Item No,15.73 PWD SR 2016-17	Sqm	26.0	Rupees Twenty Six Only
4	148.93	KSRRB M800-7. Painting:-Providing and applying two coats of ready mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications. MORTH Specification No. 803 - Painting on Steel Surface(Page no.184, item no.24.8.1)	Sqm	60.0	Rupees Sixty Only
5	1367.3	Painting New Letter and Figures of any Shade with synthetic enamel paint black or any other approved colour to give an even shade complete as per specifications. ("i) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) " MORTH Specification No. 803 (Page no.184, item no.24.9) PWD SR 2016-17	Cm	0.8	and Eighty Paise Only
6	84.41	Conveying the excavated debries and over burden earth etc., to a lead of 10.00 Km distance by using private vehicle this includes the cost of loading and unloading charges etc., complete	Cum	100.0	Rupees One Hundred Only

Bharat.S

Signature of the Contractor

10/12

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

10/12